

Oatland Island Dock Renovation  
 Number: BID C19-16  
 Posting Date: 02/17/2019  
 Addendum # 2  
 Posting Date: 03/12/2019  
 Closing Date: 03/21/2019

The information contained in this document shall become an official part of the original document and shall be acknowledged as noted on the Certification Form (Form 1) of solicitation document in the space provided. Failure to acknowledge receipt of an addendum may result in a status of non-responsive. Firms are encouraged to review the contents of this document and to respond accordingly.

**Addendum No. 2 is being issued to provide clarification:**

Questions	Response
1. Do concrete beams have to be lightweight concrete?	<b><i>Concrete beams can be either normal concrete or lightweight concrete.</i></b>
2. Will the Trex deck be salvaged?	<b><i>Drawing EX1.0, Note D2 should be replaced by the following note: "Remove and dispose of existing Trex deck."</i></b>
3. What grade of stainless steel is to be used?	<b><i>The stainless steel element materials are specified in Section 03 45 00 – Structural Steel Framing, paragraph 2.1 &amp; 2.1; and in section 05 55 00 – Metal Fabrications, throughout. Section 03 45 00 – Precast Structural Concrete, paragraph 2.04 clearly defines the grade of stainless steel materials. The description in Section 03 45 00 is the same for Section 05 12 00 and for Section 05 55 00.</i></b>
4. Will safety fencing and signage be required for the work area to keep the public out of the construction area?	<b><i>Section 01 50 00 Temporary Facilities and Control outlines fencing for the construction site. Provide Chain-Link Fencing (6' height) extend from the creek bank top on one side of the construction site to the creek bank top of the other side of the construction site. Provide enough fencing to incorporate project construction storage and project control. Construction work area signage will be required.</i></b>

5. A revised project manual has been uploaded to the District's website.
6. The Department of Natural Resources final permit packet has been uploaded to the District's website.
7. The Contractor must post temporary manatee awareness signage during construction of the facility and permanent posting and maintenance of the informal display signage, "Manatee Basics for Boaters" post-construction (as specified in DNR final permit package).

**\*\*\*ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED\*\*\***

**End of Addendum #2 to BID C19-16 Oatland Island Dock Renovation**